November 5th, 2026

Community Notice - Proposed repairs to the 5 min trail

Cadillac Mines Corporation wishes to inform residents of McGarry Township of proposed culvert repairs on the 5 min trail. Water is no longer flowing through the existing culverts, and replacement is needed before winter to restore drainage and prevent flooding of the trail.

We propose replacing the existing culverts with one larger culvert and adding fill to raise the trail. The purpose of this work is to improve drainage and maintain access as previously agreed in 2023. We would like to complete the work before the ground freezes.

The proposed work is outlined below.

Timeline and Operations

Operations expect to begin in early November, while the ground remains unfrozen. We expect the work would take up to 2 days.

What to Expect

Trail maintenance

- Replace the three existing 6-inch-diameter culverts with one 12-inch-diameter culvert.
- Excavate ditches upstream of the trail to redirect water toward the new culvert.
- Add fill to raise the trail by 1.5 feet and provide adequate culvert cover.

Safety and Environment

Cadillac Mines and its contractors maintain established operational standards:

- Clearly marked safety perimeters and signage around active work areas
- Spill prevention systems at all fuel and fluid storage locations
- Progressive site restoration upon completion
- Temporary silt barriers will be installed during the work to help limit sediment movement.

All work is being carried out within the scope of Cadillac Mines Corporation's exclusive exploration rights, in compliance with Ontario's Mining Act, the Occupational Health and Safety Act, and all applicable environmental regulations.

If you have questions or concerns about the proposed 5 min trail repairs, please contact our Community Relations team at the following email address and phone number: contact@cadillacmines.com | 705-998-4392. This will ensure that residents can communicate their feedback directly to our team and receive clear answers.

Corporate Office
123 Front Street West, Suite 905
Toronto, ON M5J 2M2

705-998-4392
contact@cadillacmines.com
www.cadillacmines.com

Project Office
1 Kerr Mine Road
Virginiatown, ON P0K 1X0